



U.S. Department
of Transportation
**Federal Highway
Administration**

May 26, 2020

1200 New Jersey Ave., SE
Washington, D.C. 20590

In Reply Refer To:
HSST-1/B-338

Mr. Ahmad Hammad
WSP USA Inc.
2200 Western Court, Suite 120
Lisle, IL 60532
USA

Dear Mr. Hammad:

This letter is in response to your January 29, 2020 request for the Federal Highway Administration (FHWA) to review a roadside safety device, hardware, or system for eligibility for reimbursement under the Federal-aid highway program. This FHWA letter of eligibility is assigned FHWA control number B-338 and is valid until a subsequent letter is issued by FHWA that expressly references this device.

Decision

The following device is eligible within the length-of-need, with details provided in the form which is attached as an integral part of this letter:

- Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels

Scope of this Letter

To be found eligible for Federal-aid funding, new roadside safety devices should meet the crash test and evaluation criteria contained in the American Association of State Highway and Transportation Officials' (AASHTO) Manual for Assessing Safety Hardware (MASH). However, the FHWA, the Department of Transportation, and the United States Government do not regulate the manufacture of roadside safety devices. Eligibility for reimbursement under the Federal-aid highway program does not establish approval, certification or endorsement of the device for any particular purpose or use.

This letter is not a determination by the FHWA, the Department of Transportation, or the United States Government that a vehicle crash involving the device will result in any particular outcome, nor is it a guarantee of the in-service performance of this device. Proper manufacturing, installation, and maintenance are required in order for this device to function as tested.

This finding of eligibility is limited to the crashworthiness of the system and does not cover other structural features, nor conformity with the Manual on Uniform Traffic Control Devices.

Eligibility for Reimbursement

Based solely on a review of crash test results and certifications submitted by the manufacturer, and the crash test laboratory, FHWA agrees that the device described herein meets the crash test and evaluation criteria of the AASHTO's MASH. Therefore, the device is eligible for reimbursement under the Federal-aid highway program if installed under the range of tested conditions.

Name of system: Constant Slope Barrier on Cantilevered Bridge Deck with Noise
Abatement Wall Panels

Type of system: Bridge Barrier

Test Level: MASH Test Level 5 (TL5)

Testing conducted by: Texas A&M Transportation Institute

Date of request: January 29, 2020

FHWA concurs with the recommendation of the accredited crash testing laboratory on the attached form.

Full Description of the Eligible Device

The device and supporting documentation, including reports of the crash tests or other testing done, videos of any crash testing, and/or drawings of the device, are described in the attached form.

Notice

This eligibility letter is issued for the subject device as tested. Modifications made to the device are not covered by this letter. Any modifications to this device should be submitted to the user (i.e., state DOT) as per their requirements.

You are expected to supply potential users with sufficient information on design, installation and maintenance requirements to ensure proper performance.

You are expected to certify to potential users that the hardware furnished has the same chemistry, mechanical properties, and geometry as that submitted for review, and that it will meet the test and evaluation criteria of AASHTO's MASH.

Issuance of this letter does not convey property rights of any sort or any exclusive privilege. This letter is based on the premise that information and reports submitted by you are accurate and correct. We reserve the right to modify or revoke this letter if: (1) there are any inaccuracies in the information submitted in support of your request for this letter, (2) the qualification testing was flawed, (3) in-service performance or other information reveals safety problems, (4) the system is significantly different from the version that was crash tested, or (5) any other information indicates that the letter was issued in error or otherwise does not reflect full and complete information about the crashworthiness of the system.

Standard Provisions

- To prevent misunderstanding by others, this letter of eligibility designated as FHWA control number B-338 shall not be reproduced except in full. This letter and the test documentation upon which it is based are public information. All such letters and documentation may be reviewed upon request.
- This letter shall not be construed as authorization or consent by the FHWA to use, manufacture, or sell any patented system for which the applicant is not the patent holder.
- This FHWA eligibility letter is not an expression of any Agency view, position, or determination of validity, scope, or ownership of any intellectual property rights to a specific device or design. Further, this letter does not impute any distribution or licensing rights to the requester. This FHWA eligibility letter determination is made based solely on the crash-testing information submitted by the requester. The FHWA reserves the right to review and revoke an earlier eligibility determination after receipt of subsequent information related to crash testing.

Sincerely,

A handwritten signature in blue ink that reads "Michael S. Griffith". The signature is written in a cursive style.

Michael S. Griffith
Director, Office of Safety Technologies
Office of Safety

Enclosures

Request for Federal Aid Reimbursement Eligibility of Highway Safety Hardware

Submitter	Date of Request:	January 29, 2020	<input checked="" type="radio"/> New <input type="radio"/> Resubmission
	Name:	Paul Kovacs, P.E., Chief Engineering Officer	
	Company:	Illinois State Toll Highway Authority	
	Address:	2700 Ogden Avenue, Downers Grove, IL 60515	
	Country:	USA	
To:	Michael S. Griffith, Director FHWA, Office of Safety Technologies		

I request the following devices be considered eligible for reimbursement under the Federal-aid highway program.

Device & Testing Criterion - Enter from right to left starting with Test Level

!-!-!

!-!-!

System Type	Submission Type	Device Name / Variant	Testing Criterion	Test Level
'B': Rigid/Semi-Rigid Barriers (Roadside, Median, Bridge Railings)	<input checked="" type="radio"/> Physical Crash Testing <input type="radio"/> Engineering Analysis	Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels	AASHTO MASH	TL5

By submitting this request for review and evaluation by the Federal Highway Administration, I certify that the product(s) was (were) tested in conformity with the AASHTO Manual for Assessing Safety Hardware and that the evaluation results meet the appropriate evaluation criteria in the MASH.

Individual or Organization responsible for the product:

Contact Name:	Ahmad Hammad, PhD, PE, SE	Same as Submitter <input type="checkbox"/>
Company Name:	WSP USA Inc.	Same as Submitter <input type="checkbox"/>
Address:	2200 Western Court, Suite 120, Lisle, IL 60532	Same as Submitter <input type="checkbox"/>
Country:	USA	Same as Submitter <input type="checkbox"/>

Enter below all disclosures of financial interests as required by the FHWA 'Federal-Aid Reimbursement Eligibility Process for Safety Hardware Devices' document.

Texas A&M Transportation Institute (TTI) was contracted by WSP USA Inc. (WSP) to perform full-scale crash testing of the 6-ft Tall Illinois Tollway Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels. There are no shared financial interests in the 6-ft Tall Illinois Tollway Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels by TTI, or between WSP and TTI, other than costs involved in the actual crash tests and reports for this submission to FHWA. **690900-ITG4-6**

PRODUCT DESCRIPTION

- New Hardware or Significant Modification
 Modification to Existing Hardware

The installation was 90 ft- $\frac{1}{2}$ -inch long, and consisted of a 6-ft tall, combination constant slope (44 inches tall) and vertical face (28 inches tall), reinforced concrete barrier anchored to a cantilevered reinforced concrete deck. A $\frac{1}{2}$ -inch joint in the deck and barrier was located 30 ft from the upstream end of the installation. W8x48 posts were secured to the back of the barrier, spaced at 11 ft-8 inches on center. These posts supported noise abatement wall panels that extended to 18 ft above grade.

CRASH TESTING

By signature below, the Engineer affiliated with the testing laboratory, agrees in support of this submission that all of the critical and relevant crash tests for this device listed above were conducted to meet the MASH test criteria. The Engineer has determined that no other crash tests are necessary to determine the device meets the MASH criteria.

Engineer Name:	D. Lance Bullard, Jr. P.E.	
Engineer Signature:	D. Lance Bullard, Jr.	Digitally signed by D. Lance Bullard, Jr. Date: 2020.01.26 10:11:43-06'00'
Address:	3100 SH47, Bldg 7091, Bryan TX 77807	Same as Submitter <input type="checkbox"/>
Country:	USA	Same as Submitter <input type="checkbox"/>


A brief description of each crash test and its result:

Required Test Number	Narrative Description	Evaluation Results
5-10 (1100C)	<p>Test 5-10 involves an 1100C vehicle impacting the test article at a target impact speed of 62 mi/h \pm2.5 mi/h and a target impact angle of 25° \pm1.5°. The target CIP was determined using the information provided in MASH Section 2.2.1, Section 2.3.2, and Table 2-7 and was for the left corner of the front bumper to impact at 3.6 ft upstream of the barrier joint.</p> <p>The results of the test conducted on September 18, 2019, are found in TTITest Report number 690900-ITG4-6. The test vehicle was traveling at an impact speed of 60.6 mi/h as it made contact with the barrier 3.8 ft upstream of the barrier joint at an impact angle of 26.3°. After loss of contact with the barrier, the vehicle came to rest 160 ft downstream of the impact point and 15 ft towards the traffic side.</p> <p>The barrier contained and redirected the 1100C vehicle. The vehicle did not penetrate, underide, or override the installation. The 1100C vehicle exited within the exit box criteria.</p> <p>Working width was 37-1/2 inches to the field side of post support protrusions. There was no measurable dynamic deflection during the test, or permanent deformation observed afterwards, for either the barrier or the wall.</p> <p>No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.</p> <p>Maximum exterior crush to the vehicle was 8.0 inches in the front plane at the left front corner at bumper height. Maximum occupant compartment deformation was 3.0 inch in the left floor pan and firewall area.</p> <p>The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 20° and 9°, respectively. Longitudinal OIV was 22.6 ft/s, and lateral OIV was 31.2 ft/s. Longitudinal occupant ridedown acceleration was 2.9g, and lateral occupant ridedown acceleration 10.6g. The occupant risk factors were within the MASH preferred limits.</p> <p>The 6-ft tall Illinois Tollway Constant Slope Barrier with Noise Abatement Wall Panels performed acceptably for MASH test 5-10.</p>	PASS

Required Test Number	Narrative Description	Evaluation Results
5-11 (2270P)	<p>Test 5-11 involves a 2270P vehicle impacting the test article at a target impact speed of 62 mi/h \pm2.5 mi/h and a target impact angle of 25° \pm1.5°. The target CIP was determined using the information provided in MASH Section 2.2.1, Section 2.3.2, and Table 2-7 and was for the left corner of the front bumper to impact at 4.3 ft upstream of the barrier joint.</p> <p>The results of the test conducted on September 19, 2019 are found in TTI Test Report number 690900-ITG4-6. The test vehicle was traveling at an impact speed of 63.2 mi/h as it made contact with the barrier 4.9 ft upstream of the barrier joint at an angle of 26.4°. After loss of contact with the barrier, the vehicle came to rest 209 ft downstream of the impact point and 60 ft towards the traffic side.</p> <p>The barrier contained and redirected the 2270P vehicle. The vehicle did not penetrate, underide, or override the installation. The 2270P vehicle exited within the exit box criteria.</p> <p>Working width was 37 1/2-inches to the field side of post support protrusions. There was no measurable dynamic deflection during the test, or permanent deformation observed afterwards, for either the barrier or the wall.</p> <p>No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.</p> <p>Maximum exterior crush to the vehicle was 14.0 inches in the front plane at the left front corner at bumper height. Maximum occupant compartment deformation was 3.0 inches in the left front firewall and kick panel area.</p> <p>The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 23° and 3°, respectively. Longitudinal OIV was 17.7 ft/s, and lateral OIV was 30.5 ft/s. Longitudinal occupant ride down acceleration was 7.3 g, and lateral occupant ride down acceleration 14.3 g. The occupant risk factors were within the MASH preferred limits.</p> <p>The 6-ft tall Illinois Tollway Constant Slope Barrier with Noise Abatement Wall Panels performed acceptably for MASH test 5-11.</p>	PASS

5-12 (36000V)	<p>Test 5-12 involves a 36000V vehicle impacting the test article at a target impact speed of 50 mi/h \pm2.5 mi/h and a target impact angle of 15° \pm1.5°. The target CIP was determined using the information provided in MASH Section 2.2.1, Section 2.3.2, and Table 2-7 and to impact at 1 ft downstream of the barrier joint.</p> <p>The results of the test conducted on September 25, 2019 are found in TTI Test Report number 690900-ITG4-6. The test vehicle was traveling at an impact speed of 50.3 mi/h as it made contact with the barrier 0.9 ft downstream of the barrier joint at an angle of 14.6°. After loss of contact with the barrier, the vehicle came to rest 240 ft downstream of the impact point and 90 ft towards the field side.</p> <p>The barrier contained and redirected the 36000V vehicle. The vehicle did not penetrate, underide, or override the installation. The 36000V vehicle exited within the exit box criteria.</p> <p>Working width was 39.6 inches to the field side of post support protrusions. During the test the maximum dynamic deflection was 2.1 inches at the top of the noise abatement wall panel. The maximum permanent deformation was 0.5 inch at the top of the barrier just downstream of the joint.</p> <p>No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.</p> <p>Maximum exterior crush to the vehicle was 14.0 inches in the front plane at the left front corner at bumper height. Maximum occupant compartment deformation was 0.5 inch at the left side floor pan.</p> <p>The 36000V vehicle remained upright during and after the collision event. Maximum roll was 6°. Longitudinal OIV was 2.6 ft/s, and lateral OIV was 11.8 ft/s. Longitudinal occupant ride down acceleration was 5.9 g, and lateral occupant ride down acceleration 12.6 g. The occupant risk factors were within the MASH preferred limits.</p> <p>The 6-ft tall Illinois Tollway Constant Slope Barrier with Noise Abatement Wall Panels performed acceptably for MASH test 5-12.</p>	PASS
5-20 (1100C)	This product is not a transition system.	Non-Relevant Test, not conducted
5-21 (2270P)	This product is not a transition system.	Non-Relevant Test, not conducted
5-22 (36000V)	This product is not a transition system.	Non-Relevant Test, not conducted

Full Scale Crash Testing was done in compliance with MASH by the following accredited crash test laboratory (cite the laboratory's accreditation status as noted in the crash test reports.):

Laboratory Name:	TexasA&M Transportation Institute	
Laboratory Signature:	Digitally signed by Darrell L. Kuhn 'Date: 2020.01.29 09:41:49 -06'00	
Address:	3100SH47, Bldg 7091, Bryan TX 77807	Same as Submitter <input type="checkbox"/>
Country:	USA	Same as Submitter <input type="checkbox"/>
Accreditation Certificate Number and Dates of current Accreditation period :	ISO 17025-2017 Laboratory A2LA Certificate Number: 2821.01 Valid To: April 30, 2021	

Submitter Signature*: Paul D. Kovacs  Digitally signed by Paul D. Kovacs
Date: 2020.01.31 16:25:32 -06'00

Submit Form


ATTACHMENTS

Attach to this form:

- 1) Additional disclosures of related financial interest as indicated above.
- 2) A copy of the full test report, video, and a Test Data Summary Sheet for each test conducted in support of this request.
- 3) A drawing or drawings of the device(s) that conform to the Task Force-13 Drawing Specifications [[Hardware Guide Drawing Standards](#)]. For proprietary products, a single isometric line drawing is usually acceptable to illustrate the product, with detailed specifications, intended use, and contact information provided on the reverse. Additional drawings (not in TF-13 format) showing details that are relevant to understanding the dimensions and performance of the device should also be submitted to facilitate our review.

FHWA Official Business Only:

Eligibility Letter		Key Words
Number	Date	



General Information

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No. MASH Test 5-10
 TTI Test No. 690900-ITG4
 Test Date 2019-09-18

Test Article

Type Longitudinal Barrier – Concrete Bridge Rail
 Name..... 6-ft tall Illinois Tollway Constant Slope
 Barrier on cantilevered bridge deck with
 noise abatement wall panels
 Installation Length..... 90 ft-½ inch
 Material or Key Elements. 6-ft tall reinforced concrete constant slope
 concrete barrier anchored to cantilevered
 reinforced concrete deck with noise
 abatement wall panels that extend to 18 ft
 above grade

Soil Type and Condition ... Concrete Deck, Dry

Test Vehicle

Type/Designation..... 1100C
 Make and Model 2009 Kia Rio
 Curb..... 2411 lb
 Test Inertial..... 2429 lb
 Dummy 165 lb
 Gross Static 2594 lb

Impact Conditions

Speed 60.6 mi/h
 Angle 26.3°
 Location/Orientation 3.8 ft upstream of
 joint

Impact Severity..... 59 kip-ft

Exit Conditions

Speed 49.9 mi/h
 Trajectory/Heading Angle... 4.3° / 4.1°

Occupant Risk Values

Longitudinal OIV 22.6 ft/s
 Lateral OIV 31.2 ft/s
 Longitudinal Ridedown..... 2.9 g
 Lateral Ridedown 10.6 g
 THIV 11.8 m/s
 ASI..... 2.73 g
 Max. 0.050-s Average
 Longitudinal -12.8 g
 Lateral..... 18.8 g
 Vertical..... -4.5 g

Post-Impact Trajectory

Stopping Distance 160 ft downstream
 15 ft toward traffic

Vehicle Stability

Maximum Yaw Angle..... 58°
 Maximum Pitch Angle..... 9°
 Maximum Roll Angle..... 20°
 Vehicle Snagging..... No
 Vehicle Pocketing..... No


Test Article Deflections

Dynamic..... None
 Permanent..... None
 Working Width, Wall 37.5 inches
 Height of Working Width, Wall 18 ft

Vehicle Damage

VDS..... 11LFQ4
 CDC 11FLEW4
 Max. Exterior Deformation 8.0 inches
 OCDI FL0110000
 Max. Occupant Compartment
 Deformation..... 3.0 inches

Figure 5.7. Summary of Results for MASH Test 5-10 on 6-ft Tall Illinois Tollway Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels.



General Information

Test Agency Texas A&M Transportation Institute (TTI)
 Test Standard Test No. MASH Test 5-11
 TTI Test No. 690900-ITG5
 Test Date 2019-09-19

Test Article

Type Longitudinal Barrier – Concrete Bridge Rail
 Name 6-ft Tall Illinois Tollway constant slope barrier on cantilevered bridge deck with noise abatement wall panels
 Installation Length 90 ft-½ inch
 Material or Key Elements 6-ft tall reinforced concrete constant slope concrete barrier anchored to cantilevered reinforced concrete deck with noise abatement wall panels that extend to 18 ft above grade

Soil Type and Condition ... Concrete Deck, Dry

Test Vehicle

Type/Designation 2270P
 Make and Model 2013 RAM 1500 Pickup
 Curb 4940 lb
 Test Inertial 5002 lb
 Dummy 165 lb
 Gross Static 5167 lb

Impact Conditions

Speed 63.2 mi/h
 Angle 26.4°
 Location/Orientation 4.9 ft upstream of barrier joint

Impact Severity 132 kip-ft

Exit Conditions

Speed 50.3 mi/h
 Trajectory/Heading Angle... 4.3° / 8.0°

Occupant Risk Values

Longitudinal OIV 17.7 ft/s
 Lateral OIV 30.5 ft/s
 Longitudinal Ridedown 7.3 g
 Lateral Ridedown 14.3 g
 THIV 10.9 m/s
 ASI 2.23

Max. 0.050-s Average

Longitudinal -8.8 g
 Lateral 17.3 g
 Vertical -3.6 g

Post-Impact Trajectory

Stopping Distance 209 ft downstream
 60 ft toward traffic

Vehicle Stability

Maximum Yaw Angle 77°
 Maximum Pitch Angle 3°
 Maximum Roll Angle 23°
 Vehicle Snagging No
 Vehicle Pocketing No


Test Article Deflections

Dynamic None
 Permanent None
 Working Width, Wall 37.5 inches
 Height of Working Width, Wall... 18 ft

Vehicle Damage

VDS 11LFQ5
 CDC 11FLEW4
 Max. Exterior Deformation 14.0 inches
 OCDI FLO010000
 Max. Occupant Compartment Deformation 3.0 inches

Figure 6.8. Summary of Results for MASH Test 5-11 on 6-ft Tall Illinois Tollway Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels.



General Information

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No..... MASH Test 5-12
 TTI Test No..... 690900-ITG6
 Test Date..... 2019-09-25

Test Article

Type..... Longitudinal Barrier – Concrete Bridge Rail
 Name..... 6-ft Tall Illinois Tollway Constant Slope Barrier on cantilevered bridge deck with noise abatement panels
 Installation Length..... 90 ft-½ inch
 Material or Key Elements..... 6-ft tall reinforced concrete constant slope concrete barrier anchored to cantilevered reinforced concrete deck with noise abatement wall panels that extend to 18 ft above grade

Soil Type and Condition... Concrete Deck, Dry

Test Vehicle

Type/Designation..... 36000V
 Make and Model..... 1998 Freightliner w/1998 Wabash 53-ft
 Curb..... 28,630 lb
 Test Inertial..... 79,130 lb
 Dummy..... No dummy
 Gross Static..... 79,130 lb

Impact Conditions

Speed..... 50.3 mi/h
 Angle..... 14.6°
 Location/Orientation..... 0.9 ft downstream of barrier joint

Impact Severity..... 425 kip-ft

Exit Conditions

Speed..... 41.7 mi/h
 Trajectory/Heading Angle... 8.1° / 0.1°

Occupant Risk Values
 (using data at fifth wheel)

Longitudinal OIV..... 2.6 ft/s
 Lateral OIV..... 11.8 ft/s
 Longitudinal Ridedown..... 5.9 g
 Lateral Ridedown..... 12.6 g
 THIV..... 3.7 m/s
 ASI..... 0.60
 Max. 0.050-s Average..... -2.2 g
 Longitudinal..... 5.3 g
 Lateral..... 3.2 g
 Vertical.....

Post-Impact Trajectory

Stopping Distance..... 240 ft downstream
 90 ft twd field side

Vehicle Stability

Maximum Yaw Angle..... 20°
 Maximum Pitch Angle..... 4°
 Maximum Roll Angle..... 6°
 Vehicle Snagging..... No
 Vehicle Pocketing..... No


Test Article Deflections

Dynamic, Wall..... 2.1 inches
 Permanent, Barrier..... 0.5 inch
 Working Width, Wall..... 39.6 inches
 Height of Working Width, Wall..... 18 ft


Vehicle Damage

VDS..... NA
 CDC..... NA
 Max. Exterior Deformation..... 14.0 inches
 OCDI..... NA
 Max. Occupant Compartment Deformation..... 0.5 inch

Figure 7.9. Summary of Results for MASH Test 5-12 on 6-ft Tall Illinois Tollway Constant Slope Barrier on Cantilevered Bridge Deck with Noise Abatement Wall Panels.

 <p>Proving Ground 3100 SH 47, Bldg 7091 Bivan, TX 77807</p> <p>Texas A&M University College Station, TX 77843 Phone 979-845-6375</p>	QF 7.4-01 Test Item Preparation/Installation Specifications	Doc. No. QF 7.4-01	Revision Date: 2018-07-08
		Quality Form	Revised by: W. L. Menges Approved by: D. L. Kuhn

The information contained in this document is confidential to TTI Proving Ground

TTI Project No./Name: 690900-ITG	Test Item Identification: Single Slope and F-Shape with Bridge Deck
Principal Investigator (PI): Akram Abuodeh	Initial Drawing Date: 2018-11-06
Sponsor: Illinois Tollway GEC	Phone: 630-241-6800 ext 4196
Name of Sponsor Representative: Ahmad Hammad	e-mail address: Ahmad.Hammad@wsp.com
Sponsor Approval Signature: N/A	Approval Date: 2018-11-06
PI Approval: 	Approval Date: 2018-11-06


-Briefly summarize revision, date revision made, and initials of who approved the change.

Date of Revision:	Brief Description of Revision:	Approved by:
2019-02-12	Modified rebar names	BLG
2019-02-13	Removed Galvanize notes, changed detail on NWA	BLG
2019-05-30	Added last three pages showing camera locations and Strain Gauge information	BLG
2019-06-10	Split F-Shape and Single Slope Strain Gauge information	BLG
2019-07-08	Removed Expansion Joint from Wall and working slab, Modified Epoxy Call-out, Added details on strain gauge/rebar information	BLG
2019-07-23	Modified location of strain gauges, modified quantity of rebar with strain gauges, swapped barriers, reduced height of wall	BLG
2019-08-15	F-Shape NAW Post, modified welded connection to a bolted connection between the W8 and W10.	BLG


Printed Name of Sponsor Representative, if other than name listed above:

Alternate Sponsor Representative Signature:

Date:

 <p>Proving Ground 3100 SH 47, Bldg 7091 Bivan, TX 77807</p> <p>Texas A&M University College Station, TX 77843 Phone 979-845-6375</p>	QF 7.4-01 Test Item Preparation/Installation Specifications	Doc. No. QF 7.4-01	Revision Date: 2018-07-08
		Quality Form	Revised by: W. L. Menges Approved by: D. L. Kuhn

The information contained in this document is confidential to TTI Proving Ground

TTI Project No./Name: 690900-ITG	Test Item Identification: Single Slope and F-Shape with Bridge Deck
Principal Investigator (PI): Akram Abuodeh	Initial Drawing Date: 2018-11-06
Sponsor: Illinois Tollway GEC	Phone: 630-241-6800 ext 4196
Name of Sponsor Representative: Ahmad Hammad	e-mail address: Ahmad.Hammad@wsp.com
Sponsor Approval Signature: N/A	Approval Date: 2018-11-06
PI Approval: 	Approval Date: 2018-11-06


-Briefly summarize revision, date revision made, and initials of who approved the change.

Date of Revision:	Brief Description of Revision:	Approved by:
2019-08-22	Added, Piles and Dowels to Deck, Added Flat Washers to Bolted connection, Updated FShape rebar	BL-G

Printed Name of Sponsor Representative, if other than name listed above:


Alternate Sponsor Representative Signature:


Date:



REINFORCEMENT BARS
 REINFORCEMENT BARS, INCLUDING EPOXY-COATED REINFORCEMENT BARS, SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-31 (ASTM A706), GRADE 60, DEFORMED BARS.

CAST-IN-PLACE CONCRETE
 ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" X 45° CHAMFER, EXCEPT WHERE SHOWN OTHERWISE.
 ALL CONCRETE = 4,000 PSI

		Roadside Safety and Physical Security Division - Proving Ground	
Project #690900-ITG FShape and Single Slope			2019-08-22
Drawn by BLG	Scale 1:225	Sheet 1 of 35 Test Installation	



Single Slope
End View



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG

Scale 1:30

Sheet 2 of 35 Single Slope End




**Section A-A
Single Slope
Away from NAW Posts**

- 4a.** All Rebar is 60 ksi rated
- 4b.** All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:25	Sheet 4 of 35 Single Slope bar Locations




Detail E




Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:13	Sheet 5 of 35
Single Slope bar Locations 2		



Section B-B
Single Slope




- 6a.** All Rebar is 60 ksi rated
- 6b.** All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:20	Sheet 6 of 35 Single Slope at Post



Single Slope Plan View

G
Sheet 8

H
Sheet 8



Single Slope Elevation View

1/2" Joint
No rebar or Dowels
3 places

I
Sheet 9

J
Sheet 9



Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG


Scale 1:125

Sheet 7 of 35 Single Slope Deck Views

Detail G

Single Slope at
Expansion Joint

4-1/2" Cover to DCKA(E) bar
5" Typ. for
DCKA (E) and a(E) bars




10" Typ. for
a1(E) and a2(E) bars
5-5/8" Cover
for a1(E) and a2(E) bars

Detail H

Single Slope at
End Region transition to Interior Region

a1(E), #5 Bar, Interior Region
DCKA(E), #8 bar End Region



End Region stops 15' from ends Interior Region Starts 15' from ends

- 8a. All Rebar is 60 ksi rated
- 8b. All Epoxy Coated Rebar is designated with (E)




Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:30	Sheet 8 of 35 SS Deck Rebar Locations


Detail I

Single Slope barrier
at Expansion Joint



Detail J

Single Slope Barrier at
end region to
interior region transition





- 9a. All Rebar is 60 ksi rated
- 9b. All Epoxy Coated Rebar is designated with (E)




Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:20	Sheet 9 of 35 SS Barrier Rebar Locations






Angle, 6"x4"x3/4"
2 needed per post



Stiffner Plate, 1/2" thick
8 needed per post



Custom Right Angle Anchor
F1554 Grd 105
4 needed per post

11a. All Steel plate, beams and angles shall be A36 (minimum 36 ksi yield) material



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG

Scale 1:10

Sheet 11 of 35 SS Post Build Up Details



End View
F-Shape



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG

Scale 1:30

Sheet 12 of 35 FShape End View



End View
F-Shape

13a. All Rebar is 60 ksi rated

13b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG

Scale 1:30

Sheet 13 of 35 FShape bar Callout



14a. All Rebar is 60 ksi rated

14b. All Epoxy Coated Rebar is designated with (E)

End View
F-Shape



Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope


2019-08-22

Drawn by BLG

Scale 1:15

Sheet 14 of 35 FShape bar Callout, 2

N
Sheet 16



Section C-C
F-Shape at Extension

15a. All Rebar is 60 ksi rated

15b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG


Scale 1:30

Sheet 15 of 35 FShape bar Location




Detail N
Scale 1 : 15

16a. All Rebar is 60 ksi rated
16b. All Epoxy Coated Rebar is designated with (E)

		Roadside Safety and Physical Security Division - Proving Ground	
Project #690900-ITG FShape and Single Slope		2019-08-22	
Drawn by BLG	Scale 1:30	Sheet 16 of 35 FShape bar Location, 2	

See Detail T for Bolt Pattern



Section D-D


17a. All Rebar is 60 ksi rated

17b. All Epoxy Coated Rebar is designated with (E)




Roadside Safety and Physical Security Division - Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:20	Sheet 17 of 35 FShape Ext. Rebar Loc.



Roadside Safety and
Physical Security Division -
Proving Ground




Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:12	Sheet 18 of 35 FShape Extension Detail



a1(E), #5 Bar



a2(E), #5 Bar



19a. All Rebar is 60 ksi rated

19b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:25


Sheet 19 of 35 Deck Rebar Details




SS(E), #5 bar




SS1(E), #5 bar
Interiors



SS2(E), #5 bar
Interiors




SSA(E), #5 bar



SS1A(E), #6 Bar
Ends

Only difference is
Rebar size and dimensions shown




SS2A(E), #6 Bar
Ends

- 20a. All Rebar is 60 ksi rated
- 20b. All Epoxy Coated Rebar is designated with (E)




Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:25	Sheet 20 of 35 Single Slope Rebar




FS2(E), #5 bar
Interior for F-Shape




FS1(E), #6 bar
Interior for F-Shape



FSA2(E), #6 bar
for F-Shape, Ends
All other Dimensions similar to FS2(E) above





FSA1(E), #6 bar
For F-Shape, Ends
All other Dimensions similar to FS1(E) above




FS(E), #5 bar
for F-Shape

21a. All Rebar is 60 ksi rated
21b. All Epoxy Coated Rebar is designated with (E)


	Roadside Safety and Physical Security Division - Proving Ground	
	Project #690900-ITG FShape and Single Slope	2019-08-22
Drawn by BLG	Scale 1:25	Sheet 21 of 35 FShape Rebar




a3(E), #6 Bar




a4(E), #4 Hook Bar



b3(E), #4 Bar



b4(E), #4 Bar




b5(E), #4 Bar

22a. All Rebar is 60 ksi rated
 22b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and Physical Security Division - Proving Ground


Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:20	Sheet 22 of 35 FShape Extension Rebar



F-Shape Deck Plan View

P
Sheet 24

Q
Sheet 24



F-Shape Deck Elevation View



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:125

Sheet 23 of 35 FShape Deck Views



Detail P
Deck Expansion Joint



Detail Q
Deck End to Interior Region
Transition

24a. All Rebar is 60 ksi rated

24b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:35

Sheet 24 of 35 FShape Deck Detail



Detail R
Barrier at Expansion Joint



Detail S
Barrier End to Interior Region
Transition

25a. All Rebar is 60 ksi rated

25b. All Epoxy Coated Rebar is designated with (E)



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22

Drawn by BLG

Scale 1:20

Sheet 25 of 35 FShape Barrier Detail




26a. All Steel plate, beams and angles shall be A36 (minimum 36 ksi yield) material




Roadside Safety and Physical Security Division - Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:40	Sheet 26 of 35 FShape NAW Post Details


Q:\Accreditation-17025-2017\EIR-000 Project Files\690900\ITG - Illinois Tollway GEC - Akram\Drafting\Bridges Deck models\2019-08-22\690900-ITG, Bridge Deck S...



Section W-W
Scale 1 : 10



Section U-U
Scale 1 : 10



Section AG-AG
Scale 1 : 10



Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope


2019-08-22

Drawn by BLG


Scale 1:40

Sheet 27 of 35 FShape NAW Post 2


27a. All Steel plate, beams and angles shall be A36 (minimum 36 ksi yield) material




TOP PANEL




BOTTOM AND CENTER PANEL




REVEAL DETAIL



TYPICAL NOISE WALL PANEL DETAIL




TYPICAL PLAN VIEW THRU NOISE ABATEMENT WALL




BOTTOM PANEL BEARING DETAIL

* E70 ELECTRODES ARE NOT PERMITTED FOR GRADE 60 REINFORCEMENT. REFER TO AWS D1.1 TABLE 3.1 - PREQUALIFIED BASE METAL-FILLER MATERIAL COMBINATIONS FOR MATCHING STRENGTH AND AWS D1.4 TABLE 5.1 MATCHING FILLER METAL REQUIREMENTS. USE E90 ELECTRODES FOR ASTM A615 REBAR.



HORIZONTAL JOINT DETAIL



PANEL CONNECTION TO COLUMN DETAIL

27A. ALL REBAR IS 60KSI RATED
 27B. ALL REBAR IS EPOXY COATED
 27C. CONCRETE CLASS "F" WITH COMPRESSIVE STRENGTH OF 4,000PSI MINIMUM

NOISE ABATEMENT
 WALL DETAILS
 BRIDGE DECK
 SHEET 1 OF 1



Roadside Safety and
 Physical Security Division -
 Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:25

Sheet 28 of 35 Noise Abatement Wall



Single Slope Barrier




F-Shape Barrier

Go-Pro Cameras:
 Camera to be mounted on top of NAW post, facing
 along the front of the NAW toward the impact zone near
 the full joint in the barrier and deck




Roadside Safety and
 Physical Security Division -
 Proving Ground


Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:200	Sheet 29 of 35 Camera Location



Detail AB
Scale 1 : 35



#6 F-Shape
FSA2-SG-(E)
9 Needed



← Upstream Downstream →

Elevation view of Fshape deck



Roadside Safety and
Physical Security Division -
Proving Ground



Project #690900-ITG FShape and Single Slope

2019-08-22



Drawn by BLG

Scale 1:220

Sheet 30 of 35 Strain Gauges, FShape Barrier



Detail AC
Scale 1 : 30




Plan view of Fshape deck




Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:250	Sheet 31 of 35 Strain Gauges, FShape Deck



Detail AD
Scale 1 : 30



#6 Single Slope
SS2A-SG(E)
9 Needed



Elevation View of Single Slope



Roadside Safety and
Physical Security Division -
Proving Ground



Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:220

Sheet 32 of 35 Strain Gauges, SS Barrier



Detail AE
Scale 1 : 20



Plan view of Single Slope deck



Roadside Safety and
Physical Security Division -
Proving Ground

Project #690900-ITG FShape and Single Slope


2019-08-22

Drawn by BLG


Scale 1:250

Sheet 33 of 35 Strain Gauges, SS Deck

Single Slope Plan View



F-Shape Plan View



Roadside Safety and
Physical Security Division -
Proving Ground


Project #690900-ITG FShape and Single Slope

2019-08-22


Drawn by BLG

Scale 1:250

Sheet 34 of 35 Deck Pile Locations



F-Shape End View



Single Slope End View



Roadside Safety and Physical Security Division - Proving Ground

Project #690900-ITG FShape and Single Slope		2019-08-22
Drawn by BLG	Scale 1:250	Sheet 35 of 35 Concrete Location